

NASA TM-82635



3 1176 00166 6669

NASA Technical Memorandum 82635

NASA-TM-82635 19810021848

SEP Bimod Variable Conductance Acceptance and Characterization

81N30340

Joseph A. Hemminger
Lewis Research Center
Cleveland, Ohio

August 1981

LIBRARY COPY

SEP 14 1981

CANCELED
LIBRARY, NASA
HAMPTON, VIRGINIA

NASA

Lewis Research Center
Cleveland, Ohio
44135


Reply to Attn of: 1943

September 10, 1981

TO: Distribution
FROM: 1900/Chief, Management Services Division
SUBJECT: NASA Technical Memorandums

Enclosed are copies of Lewis Technical Memorandums for your
information and library use.

Please direct them to the attention of the members of your technical staff
who may be interested in the subjects.



George Mandel

Distribution:

Installation Libraries

Ames Research Center
Hugh L. Dryden Flight Research Center
Goddard Space Flight Center
Jet Propulsion Laboratory
John F. Kennedy Space Center
Langley Research Center
Lyndon B. Johnson Space Center
George C. Marshall Space Flight Center
Wallops Flight Center

TABLE OF CONTENTS

	<u>Page</u>
1.0 SUMMARY	1
2.0 Introduction	2
3.0 Description of Hardware Tested	3
4.0 Description of Test Equipment and Setup	8
5.0 Test Plan	14
6.0 Test Procedure	15
7.0 Test Results	17
8.0 Evaluation and Conclusions	34
9.0 References	35
Appendixes	36
A - Detailed Temperature and Heater Power Data	36
B - Drawings	170

1.0 SUMMARY

A series of six heat pipes, similar in design to those flown on the Communications Technology Satellite Hermes, were fabricated and tested by TRW Space Systems Group for use by NASA Lewis Research Center in a prototype Solar Electric Propulsion BIMOD thrust module. This report documents the results of acceptance and characterization tests performed on the heat pipe subassemblies following their delivery to NASA. The performance of all the heat pipes met, or exceeded, design specifications.

2.0 INTRODUCTION

As part of its Technology Readiness Program for Solar Electric Propulsion (SEP), NASA Lewis Research Center designed and built a prototype SEP BIMOD* thrust module. One of the primary goals of this effort was to minimize the individual weights of primary system components. For the two Power Processing Units (PPU's) in the BIMOD assembly, this was done through an integrated evaluation of thermal control and structural requirements. The resulting design (which is documented in detail in reference 1) called for the use of six variable conductance heat pipes to transport 410 watts of waste heat from each of the two PPU's to the two space-facing radiator panels. The heat pipes used, similar in design to those used on the Communications Technology Satellite (CTS) Hermes, were built and tested by TRW's Space Systems Group (reference 2). Prior to assembly into the "live" BIMOD configuration, the individual heat pipe subassemblies were subjected to acceptance and characterization tests at Lewis (1) to verify that their performance met design specifications, and (2) to provide reference data to compare with data taken in expected tests of the live BIMOD assembly. This report documents the hardware used in, and the results of, these tests.

*The name BIMOD is derived from the bi-modular nature of the assembly, which contains two PPU's, two 30-cm ion thrusters, and two thermal control radiator panels.

3.0 DESCRIPTION OF THE HARDWARE TESTED

TRW provided the six heat pipes to NASA in two modular configurations, designated A and B. Each module consists of three heat pipes soldered into two aluminum evaporator saddles. The two evaporator saddles differ according to the pattern of holes (with plate-nuts) used to attach PPU electrical components. Their most differentiating feature, however, is the presence on one of the saddles (Appendix B, NASA Drawing CF 637022) of an extra tab which provides an additional heat flow path for two high dissipation inductors in the PPU A-3 module. The other saddle (NASA Drawing CF 637023) does not have such a tab. "Saddle with tab" and "saddle without tab" is used to differentiate the two evaporator saddles throughout this report.

A plan view of the module subassemblies is shown in Figure 3.1. They differ according to: (1) the orientation of the two evaporator saddles on the assembly, and (2) which end of the saddles the condenser sections of the individual heat pipes exit. Figure 3.2 is a schematic of the heat pipe cross-section and Table 3.1 gives details of its mechanical configuration. Figure 3.3 is a photograph of the Module A configuration.

FIGURE 3.1 SEP BIMOD Heat Pipes: Plan & End Views of Module Subassemblies




FIGURE 3.2 SEP BIMOD Heat Pipe
Cross-Section Schematic





TABLE 3.1 Physical Details of CTS and SEP Variable Conductance Heat Pipe Systems

CHARACTERISTIC	CTS VCHPS	SEP BIMOD VCHPS
Function	Control temperature of TEP OST and PPS (in parallel with South Panel)	Control temperature of PPU's in BIMOD configuration
Number of heat pipes	Three per spacecraft	Three per PPU, or six per BIMOD
Thermal System capacity	196 watts min at $T_g \geq 500^\circ\text{C}$ (1220F) and $T_g < 3$ watts at $T_g < 100^\circ\text{C}$ (500F)	410 watts per PPU at $T_g \geq 500^\circ\text{C}$ (1220F) and < 3 watts per PPU at $T_g < 100^\circ\text{C}$ (500F)
Heat pipe capacity	Nom. 150 watts min at $T_g \geq 500^\circ\text{C}$ (1220F) and < 1 watt at $T_g < 100^\circ\text{C}$ (500F)	220 watts min at $T_g \geq 500^\circ\text{C}$ (1220F) and < 1 watt at $T_g < 100^\circ\text{C}$ (500F)
Heat pipe power factor Temp. control range Max. off. sink temp.	7500 watt-inches 21-480C (70-1180F)	14,000 watt-inches 33-470C (91-1170F) -750C (-1020F)
Tubes Material	304 stainless steel, fully annealed ($\sigma_y = 35,000$ psi; $\sigma_u = 75,000$ psi)	SAVE
Cross-section Internal threads	0.500 OD x 0.028 wall 100 TPI, 0.005 deep, 400 included angle	SAVE
Free vol/length ratio	.1027 in ³ /in	SAVE
Total length	#1 #2 #3	122.556
Evap. section length	68.00 74.86 79.78	45.188
Adiab. section length	22.00 22.00 22.00	5.368
Cond. section length	3.70 3.70 3.70	72.000
Effective length $((L_e + L_c)/2) + L_a$	42.30 49.16 54.08	63.962
Reservoirs Material Configuration	304 stainless steel Spun hemispherical cap with 1.75 OD cylindrical center section 8.22 in ³	SAVE
Free volume	SAVE	SAVE

CHARACTERISTIC	CTS VCHPS	SEP BIMOD VCHPS
Wicks Material Reservoir wick	304 stainless steel 0.020 thick (spot-welded to interior walls)	SAVE
Tube wick	0.050 thick (interference fit across dia. of tube; one splice required)	SAVE
Arteries Material Cross-section	316 stainless steel 0.063 ID x (150) ² mesh (0.0026 dia. wire)	304 stainless steel 0.070 ID x (150) ² mesh (0.0026 dia. wire); one splice required
Priming foils Material Cross-section Attachment	304 stainless steel 0.063 ID x 0.0005 wall with 0.010 dia. holes Spot-welded to end of arteries and diametral wick	SAVE 0.081 ID x 0.00027 wall with 0.006 dia. holes Welded over window in end-cap; end-cap welded to end of artery.
Working fluid Material	Methanol (Spectro-photometric grade) -980C (-1440F) 650C (1490F)	SAVE
Freezing point Boiling point Control gas Material	90% nitrogen, 10% helium (research grade)	SAVE
Evaporator saddles Material Fabrication method Attachment	6061-T6 aluminum alloy Extruded 60-40 tin/lead solder (following Cu/Ni/Sn plating)	SAVE Mached or extruded
Condenser saddles Material Fabrication method Attachment	6061-T6 aluminum alloy Extruded 60-40 tin/lead solder (following Cu/Ni/Sn plating)	SAVE Formed sheet (also serves as radiator stiffeners) RTV-566 and bolts to radiator

FIGURE 3.3 SEP BIMOD Heat Pipes:
Module A Subassembly



4.0 DESCRIPTION OF TEST EQUIPMENT AND SETUP

Figure 4.1 is a photograph of the test setup taken during tests on the Module B configuration hardware. Specifics of the major mechanical elements of the test equipment include the following.

1. Separate, resistance-type heaters were attached to each side of the evaporator section of the heat pipes to simulate the separate heat input from each PPU in the BIMOD configuration. As shown in Figures 4.2.1 and 4.2.2, heater no. 1 was attached to the evaporator saddle with the tab, and heater no. 2 to the saddle without the tab. The entire evaporator/heaters assembly was enclosed in styrofoam balls which were contained within multi-layer insulation (MLI) blankets.
2. Dual-groove aluminum saddles enclosed both the condenser section of each heat pipe and a copper tube through which fluid from a constant temperature bath (CTB) could be circulated. These saddles were left exposed to the ambient air environment.
3. Aluminum saddles with resistance-type heaters, and a stainless-steel jacket (enclosed in MLI) through which cold GN2 could be circulated, surrounded each heat pipe gas reservoir. GN2 was cooled by flowing it through a copper coil immersed in LN2. Locations of the heaters (numbered 3, 4, and 5) are shown in Figures 4.2.1 and 4.2.2).
4. A test stand with leveling screws on each leg, and a tilting top-frame to which the heat pipe subassembly was attached, provided the tilt adjustment capability required to adjust the gravity-head on the heat pipes.
5. Over-heating protection was provided. A dedicated thermocouple sensing evaporator heater temperature was used to activate relays to shut off heater power when the evaporator temperature exceeded a nominal 150°F (66°C).

FIGURE 4.1 SEP BIMOD Heat Pipe Acceptance and Characterization Tests: Hardware Setup




FIGURE 4.2.1 Thermocouple Instrumentation Layout
for Module A Configuration





FIGURE 4.2.2 Thermocouple Instrumentation Layout
for Module B Configuration



Instrumentation for the test included the following:

1. An inclinometer was used to measure the tilt of the heat pipe subassembly.
2. Digital voltmeters (DVM's) were set up to measure voltage and current applied to each heater circuit.
3. Fifty-four (54) copper/constantan thermocouple (the locations of which are shown in Figures 4.2.1 and 4.4.2) were used to measure temperatures as follows.
 - a. Five thermocouples were imbedded in each evaporator heater plate, equally spaced at 10 inches apart along the heater centerline. Numbers 1 through 5 were mounted on heater number 1 (saddle with tab) and numbers 6 through 10 on heater number 2 (saddle without tab).
 - b. Two thermocouples were epoxied to the pipe wall of the adiabatic (curved) section of each heat pipe, one on the inside of the curve and the other on the outside. These thermocouples are numbered 11 through 16, as shown in Figures 4.2.1 and 4.2.2.
 - c. Ten thermocouples were imbedded in one of the two saddles surrounding the condenser section of each heat pipe. Eight of these thermocouples were equally spaced 10 inches apart immediately adjacent to the condenser section of each heat pipe and the other two were spaced 70 inches apart (i.e. at each end of the saddle) immediately adjacent to the tube cooling the condenser saddles. These thermocouples are identified (for each heat pipe respectively) as:
 - i. Numbers 21 through 30
 - ii. Numbers 31 through 40
 - iii. Numbers 41, 57, and 43 through 50

- d. One thermocouple was imbedded in each of the two heater saddles on each heat pipe gas reservoir. These thermocouples are numbered 51 through 56, as shown in Figures 4.2.1 and 4.2.2.
- e. One thermocouple (number 58) was inserted in the fluid in the constant temperature bath (CTB) reservoir.
- f. One thermocouple (number 59) measured the temperature of the ambient air under the test stand.

Temperatures were recorded using a DORIC Digitrend (Model no. 210-100-0104 ((10 mv))-05-09; serial no. 5435; NASA LeRC property number 113122). Figures 4.2.1 and 4.2.2 show the location of the thermocouples for each of the two (2) module configurations tested and the Digitrend channels on which they were recorded.

5.0 TEST PLAN

The primary purpose of these tests was to verify that the heat pipe manufacturing specifications were met. The parameters explored for each heat pipe included its turn-on and full-on temperatures and its maximum heat transport capacity.

Secondarily, the tests were run to determine system operating characteristics, both those defining heat pipe operating limitations and those peculiar to the BIMOD configuration, which might be of value during future testing and design efforts involving such heat pipes. These latter tests included: (1) determining the heat transport capacity of a heat pipe module configuration when operating with all arteries deprimed (this parameter could be of value when ground test or flight environment conditions might cause artery depriming; throttling power consumption to this value would allow for continued operation until an orderly thermal recycling can be effected to reprime the arteries), (2) determining the temperature differential across the heat pipe evaporator when only one PPU is operating (this parameter gives an indication of the quality of thermal interface joints and saddle cross-section design in transferring heat from a PPU to the heat pipes), and (3) determining the effect of changing condenser sink temperature on heat pipe performance (this parameter is useful in determining the effect on performance resulting from varying radiator size, thickness, and sink temperatures resulting from operating in different environments, e.g., space vs. test chamber cold walls, etc.).

6.0 TEST PROCEDURE

Prior to each test run, the heat pipe system was tilted so that a 2- to 3-inch head caused the heat pipes to deprime. The system was then re-leveled and the heat pipes were given time to reprime. During actual application of heat to the heat pipe evaporators, the system was tilted slightly (the evaporator end being higher than the condenser end) so that the heat pipes were working against a 0.30-inch gravity head. This configuration worked to minimize the positive effect that gravity head has on heat pipe performance, thereby resulting in test data that was more representative of what expected zero-g performance should be.

For each heat pipe that would be operated during the test run, its gas reservoir was cooled to $-100 \pm 10^{\circ}\text{F}$ ($-73 \pm ^{\circ}\text{C}$), its specified effective sink temperature. For each heat pipe that was to be turned off, enough power was applied to its gas reservoir heater to maintain a temperature of $130 \pm 10^{\circ}\text{F}$ ($54 \pm 6^{\circ}\text{C}$). During the test run, this temperature was increased when required, to keep it approximately 5°F (3°C) above the maximum evaporator temperature.

The best turn-on and full-on temperature data was obtained when simultaneously operating all three heat pipes in a module configuration. The turn-on temperature was defined as the average adiabatic temperature when evaporator temperatures had risen to or above 80°F (27°C) and the nearest condenser temperature was within 5°F of this average adiabatic temperature. The full-on temperature was defined as the average adiabatic temperature at the time the system reached thermal equilibrium with 200 watts per operating heat pipe applied to the evaporator heaters and the temperature of the constant temperature bath (CTB) used to cool the condenser saddles set at approximately 112°F^* (44°C). The procedure for obtaining this data was as follows: A total of 60 watts was initially applied to the evaporator heaters and temperatures were recorded at approximately 5-minute intervals. When the evaporator approached the turn-on temperature, data was taken at approximately 2-minute intervals. Once the turn-on temperature was determined, the heat applied to the evaporator was increased to 600 watts (which provided the rated 200 watts input to each heat pipe). When the evaporator heaters approached the full-on temperature condition, flow from the constant temperature bath (CTB) to the condenser cooling tubes was initiated. This procedure was necessary because the condenser saddles did not have adequate surface area to convectively cool the condenser.

*This was the estimated sink temperature required to draw 220 watts of heat through the saddles, etc., cross-section when the heat pipe is running at approximately 125°F (52°C) as indicated by the adiabatic section temperature.

Once the full-on temperature was determined, power to the evaporator was increased in 10- and/or 20-watt steps until one of the heat pipes deprimed, resulting in thermal runaway of the system. The maximum capacity of a heat pipe system (module) was defined as the highest evaporator heater power setting at which the evaporator temperatures did not indicate a thermal runaway condition.

When capacity tests were run on individual heat pipes, the power applied to the evaporator heaters after the turn-on temperature was reached was 220 watts. Power was increased in 10- and/or 20-watt increments until the operating heat pipe deprimed or evaporator temperature limits were exceeded. The maximum capacity of a heat pipe was defined as the highest evaporator heater power setting at which the operating heat pipe was not deprimed.

The arteries-deprimed capacity test of a heat pipe module was conducted following the arteries-primed capacity tests. Once one heat pipe deprimed due to excessive load, the remaining ones were forced to deprime by: (1) applying an approximately 2 1/2-inch gravity head (by tilting the unit), (2) initially applying a high heat load to the evaporator and then continuously adjusting the load to keep temperatures under the 150°F (66°C) maximum limit, and (3) mechanically jarring the test assembly. The maximum capacity of the module with all arteries deprimed was defined as that power at which the 150°F (66°C) maximum temperature on the evaporator could be maintained.

The ΔT across the evaporator with only one heater on (to simulate only one PPU operating) was determined during two of the arteries-primed capacity tests. For the Module A unit, a load of 330 watts was alternately applied to each of the two evaporator heaters and the temperature distribution determined when the system came to equilibrium. For the Module B unit, 480 watts was alternately applied to the evaporator heaters.

Determining the effect of changing sink temperature on heat pipe performance was done only with the Module A unit. The constant temperature bath (CTB) was lowered in temperature to -1.7°F (-18.7°C), then in sequence, 660 watts was applied to the evaporator heaters and flow was initiated from the CTB to the condenser cooling tubes. The heat being transmitted from the evaporator through the heat pipes to the CTB fluid was more than the CTB refrigerating unit could handle and, therefore, the 17.5 gallons of fluid slowly rose in temperature. The CTB fluid temperature was allowed to rise until one heat pipe deprimed, terminating the test.

7.0 TEST RESULTS

An overview summary of the results of these tests is presented in Table 7.1. The schedule according to which the tests were run (which also indicates the sequence with which the detailed data is presented in Appendix A) is outlined in Table 7.2.

Table 7.3 presents the turn-on and full-on temperatures of the individual heat pipes and compares the results with those obtained by TRW during their acceptance testing of the heat pipes following manufacture. These temperatures represent an average of the values determined from all the tests in which a particular heat pipe was operated in its primed state. The slight differences between these and TRW's results can be attributed to combined tolerances in test equipment and minor differences in test procedures and interpretation of results. For example, TRW determined turn-on temperatures with 220 watts applied to the evaporator; these tests were initially run with 60 watts applied to the evaporator to enable the Digitrend unit to record the turn-on data. Also, TRW used a thermocouple mounted at the end of the evaporator opposite the condenser to define turn-on and full-on temperatures; these tests used the adiabatic section temperatures to define these values because all the evaporator thermocouples were mounted on the heater plates, which saw a ΔT between the plate and saddle resulting from the interface RTV joint and which varied according to the power applied to the evaporator heaters.

Table 7.4 presents turn-on and full-on temperatures taken during arteries-deprimed tests of each module configuration with simultaneous operation of all three heat pipes. Note that the turn-on temperatures are slightly higher than for the primed condition. The full-on condition, which was defined as the maximum power at which the maximum evaporator temperature is 150°F (66°C) or less, shows a configuration sensitivity. Both the individual evaporator heater elements and the thermocouples indicating evaporator temperatures were located along the centerline of the saddles, that is, closest to the center heat pipe (S/N-2 and S/N-3) in the evaporator configuration. As a result, at the low power levels at which these tests were run, the center heat pipe ran hotter, thereby carrying a greater share of the applied load.

TABLE 7.1 Summary of Results of Heat Pipe Tests

Goals	Spec.	Results
Verify for individual heat pipes		
Turn-on temperature	100°F	98 to 101°F
Full-on temperature	>122°F	123 to 125°F
Verify heat transport capacity of Individual heat pipes	Min. of 220 watts	260 to >320 watts
Three heat pipe Arteries primed	>660 watts	760 and 940 watts
subsystems Arteries deprived	---	85 and 110 watts
Determine evaporator temperature profile with one PPU operating	---	ΔT_{evap} at P_{evap}
		6.8, 7.6°F 480 watts
		4.7, 8.1°F 330 watts
Determine effect on heat pipe operating temperature resulting from changing condenser sink temperature	---	Ratio = 0.24 °F/°F (over 10 to 105°F sink temp. range)

TABLE 7.2 Test Schedule

Module Configuration	Test Date	Heat Pipes Operating	Special Test Condition(s)
B	5-17-79	3, 5, 7	Arteries Primed
	5-21-79	3	Arteries Primed
	5-29-79	5	Arteries Primed
	5-30-79	7	Arteries Primed
	5-31-79	3, 5, 7	Arteries Deprimed
A	7-3-79	2, 1, 4	Arteries Primed
	7-19-79	2	Arteries Primed
	7-23-79	1	Arteries Primed
	7-24-79	4	Arteries Primed
	7-24-79	2, 1, 4	Arteries Deprimed
	7-25-79	2, 1, 4	Arteries Primed;
	7-25-79	2, 1, 4	Arteries Primed (repeat of 7-3-79 test)

TABLE 7.3 Turn-On and Full-On Temperatures of
SEP Heat Pipes (Arteries Primed)

Module Configuration	Heat Pipe Number	Temperature (°F)			
		Turn-On		Full-On	
		LeRC	TRW	LeRC	TRW
A	1	98	103	124	123
	2	101	103	123	121
	4	99	105	124	126
B	3	101	100	125	124
	5	100	100	123	125
	7	99	105	123	126

TABLE 7.4 Turn-On and Full-On Temperatures of
SEP Heat Pipes (Arteries Deprimed)

Module Configuration	Heat Pipe Number	Temperature (°F)	
		Turn-On	Full-On
A	1	102	112
	2	105	115
	4	105	113
B	3	(Data Not Recorded)	115
	5	105	109
	7	105	105

Table 7.5 presents the maximum heat transport capacity data determined in these tests and compares the results with those obtained by TRW during testing of the heat pipes at the time of manufacture. It should be noted that the sum of the individual heat pipe capacities is greater than the capacity of the system when operated as a whole in both module configurations. The detailed thermal data shows why this takes place. As indicated in Figures 7.1 and 7.5, the adiabatic sections of Module A heat pipe S/N-4 and Module B heat pipe S/N-3 were running hotter than the other two heat pipes in their respective configurations, thereby indicating that they were encountering the highest thermal resistance relative to their applied loads. Also, as Table 7.5 indicates, their individual heat transport capacities are the lowest in their respective module configurations. Thus one would expect that these two heat pipes would deprime before the other two in the respective configurations reached their maximum capacity. The test results show that, indeed, such was the response. In Figures 7.2, 7.6 and 7.7, heat pipes S/N-4 and S/N-3 show a drop in temperature while the other heat pipes continue to rise in temperature. In the case of the Module A configuration, however, it appears that only one artery of heat pipe S/N-3 initially deprimed and that the other two heat pipes had sufficient excess capacity to compensate for its loss of capacity. As shown in Figures 7.3 and 7.4, only when additional power was applied to the evaporator heaters did heat pipe S/N-2 deprime and evaporator temperatures start running away.

Table 7.6 summarizes the results of the capacity tests of all three heat pipes in a module configuration when all their arteries are deprimed.

Figures 7.8 and 7.9 show the temperature profile of the Module B configuration when only one evaporator heater is operating at 480 watts.

Figures 7.10 and 7.11 show the Module A temperature profile when each evaporator heater is operated at 330 watts respectively.

Figure 7.12 shows a plot of varying CTB temperature vs. the corresponding adiabatic section temperatures of the heat pipes in the Module A configuration. The ratio indicated in Table 7.1 was derived from the data used to generate this figure.

Finally, the detailed temperature and heater power data has been cataloged in the figures included in Appendix A of this report. The data is presented in the form of computerized: (1) plots (which include descriptive notations of significant test events), and (2) schematics (which provide instantaneous temperature profiles at or near highlight points during the tests).

TABLE 7.5 Heat Transport Capacity of
SEP Heat Pipes (Arteries Primed)

Module Configuration	Heat Pipe Number	Heat Transport Capacity (Watts) At Artery Depriming (Burnout)		
		Spec	LeRC	TRW
A	1,2,4	>660	760 ¹	---
	1*	>220	320	230
	2	>220	320	>310 ³
	4*	>220	260	>300 ³
B	3,5,7	>660	940 ²	---
	3	>220	280	230
	5	>220	>300 ⁴	300
	7	>220	>300 ³	320

1 Heat pipe S/N-4 deprimed first.

2 Heat pipe S/N-3 deprimed first.

3 Testing terminated at this power level.

4 Test conditions resulted in other heat pipes
in module carrying part of load at this power level.

*Note: It is possible that these heat pipe I.D. numbers are the reverse of those used by TRW. This confusion resulted from the identification numbers not being inscribed on the heat pipes themselves and the fact that these two heat pipes are identical in external appearance. The results shown in this table seem to verify this apparent reversal.

TABLE 7.6 Heat Transport Capacity of
SEP Heat Pipes (Arteries Deprimed)

Module Configuration	Heat Pipe Number	Heat Transport Capacity (Watts) At Max. Evap. Temp. of 150°F
A	1,2,4	85
B	3,5,7	110

SEEP 3 MOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPLEPATING
ARTIFICES PRIMED) TEST DATE = 7U379 TIME = 1600

[illegible]

127.7** 120.0
** 122.0**
** 126.0

134.9*** 139.4

140.0***142.9

144.7
 ☆☆☆☆T=TTTT
 ☆☆☆☆
 ☆☆☆☆
 ☆☆☆☆

141.1001 144.7

139.1*** 142.3

130.1*** 137.6

126.0*

127.5

LOCATION	TEMP (DEG F)
CONSTANT TEMP BATH	110.1
AMBIENT AIR	68.6

HEATER	LOCATION	POWER (WATTS)
1	EVAP SAD W/TAB	300.1
2	EVAP SAD W/O TAB	380.1
3	S/N-2 GAS RESER	.0
4	S/N-1 GAS RESER	.0
5	S/N-4 GAS RESER	.0

78.8
38.0

-69.8
-61.1

☆☆☆☆☆
☆☆☆☆☆
☆☆☆☆☆
☆☆☆☆☆
☆☆☆☆☆
95.7
03.7

1
 2
 3
 4
 5
 6
 7
 8
 9
 10
 11
 12
 13
 14
 15
 16
 17
 18
 19
 20
 21
 22
 23
 24
 25
 26
 27
 28
 29
 30
 31
 32
 33
 34
 35
 36
 37
 38
 39
 40
 41
 42
 43
 44
 45
 46
 47
 48
 49
 50
 51
 52
 53
 54
 55
 56
 57
 58
 59
 60
 61
 62
 63
 64
 65
 66
 67
 68
 69
 70
 71
 72
 73
 74
 75
 76
 77
 78
 79
 80
 81
 82
 83
 84
 85
 86
 87
 88
 89
 90
 91
 92
 93
 94
 95
 96
 97
 98
 99
 100
 101
 102
 103
 104
 105
 106
 107
 108
 109
 110
 111
 112
 113
 114
 115
 116
 117
 118
 119
 120
 121
 122
 123
 124
 125
 126
 127
 128
 129
 130
 131
 132
 133
 134
 135
 136
 137
 138
 139
 140
 141
 142
 143
 144
 145
 146
 147
 148
 149
 150
 151
 152
 153
 154
 155
 156
 157
 158
 159
 160
 161
 162
 163
 164
 165
 166
 167
 168
 169
 170
 171
 172
 173
 174
 175
 176
 177
 178
 179
 180
 181
 182
 183
 184
 185
 186
 187
 188
 189
 190
 191
 192
 193
 194
 195
 196
 197
 198
 199
 200
 201
 202
 203
 204
 205
 206
 207
 208
 209
 210
 211
 212
 213
 214
 215
 216
 217
 218
 219
 220
 221
 222
 223
 224
 225
 226
 227
 228
 229
 230
 231
 232
 233
 234
 235
 236
 237
 238
 239
 240
 241
 242
 243
 244
 245
 246
 247
 248
 249
 250
 251
 252
 253
 254
 255
 256
 257
 258
 259
 260
 261
 262
 263
 264
 265
 266
 267
 268
 269
 270
 271
 272
 273
 274
 275
 276
 277
 278
 279
 280
 281
 282
 283
 284
 285
 286
 287
 288
 289
 290
 291
 292
 293
 294
 295
 296
 297
 298
 299
 300
 301
 302
 303
 304
 305
 306
 307
 308
 309
 310
 311
 312
 313
 314
 315
 316
 317
 318
 319
 320
 321
 322
 323
 324
 325
 326
 327
 328
 329
 330
 331
 332
 333
 334
 335
 336
 337
 338
 339
 340
 341
 342
 343
 344
 345
 346
 347
 348
 349
 350
 351
 352
 353
 354
 355
 356
 357
 358
 359
 360
 361
 362
 363
 364
 365
 366
 367
 368
 369
 370
 371
 372
 373
 374
 375
 376
 377
 378
 379
 380
 381
 382
 383
 384
 385
 386
 387
 388
 389
 390
 391
 392
 393
 394
 395
 396
 397
 398
 399
 400
 401
 402
 403
 404
 405
 406
 407
 408
 409
 410
 411
 412
 413
 414
 415
 416
 417
 418
 419
 420
 421
 422
 423
 424
 425
 426
 427
 428
 429
 430
 431
 432
 433
 434
 435
 436
 437
 438
 439
 440
 441
 442
 443
 444
 445
 446
 447
 448
 449
 450
 451
 452
 453
 454
 455
 456
 457
 458
 459
 460
 461
 462
 463
 464
 465
 466
 467
 468
 469
 470
 471
 472
 473
 474
 475
 476
 477
 478
 479
 480
 481
 482
 483
 484
 485
 486
 487
 488
 489
 490
 491
 492
 493
 494
 495
 496
 497
 498
 499
 500
 501
 502
 503
 504
 505
 506
 507
 508
 509
 510
 511
 512
 513
 514
 515
 516
 517
 518
 519
 520
 521
 522
 523
 524
 525

TEST DATE = 51779 TIME = 1649

SERIAL NO. 1

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING

CONDENSER SECTION

[illegible]

```

TOP
HEAT PIPE
(S/N-5)
132.4** 126.6** 128.3** 127.1** 126.4** 127.0** 122.5** 93.6 -41.8
**      **      **      **      **      **      **      *
**      **      **      **      **      **      **      *
**      **      **      **      **      **      **      *

```

145.6***
144.2


```

EVAPORATOR          152.6 ***** 151.5
SECTION              *****
                      *****
                      *****
                      *****
LOCATION               TEMP(DEG F)
CONSTANT TEMP       BATH    112.3
AMBIENT AIR         71.5

```

HEATER	LOCATION	POWER(WATTS)
1	EVAP SAD W TAB	0
2	EVAP SAD W/O TAB	0
3	S/N-7 GAS RESER	0
4	S/N-5 GAS RESER	0
5	S/N-7 GAS RESER	0

[illegible]

FIGURE 7.8 Temperature Profile With Power to Evaporator Heater Number 1 Only

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1 TEST DATE = 51779 TIME = 1750
 ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
 (ARTERIES PRIMED)

CONDENSER SECTION									
BOTTOM HEAT PIPE (S/N-7)	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
TOP HEAT PIPE (S/N-5)	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
EVAPORATOR SECTION	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
SINGLE HEAT PIPE (S/N-3)	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****

FIGURE 7.9 Temperature Profile With Power to Evaporator Heater Number 2 Only

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1 TEST DATE = 51779 TIME = 1800
 ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
 (ARTERIES PRIMED)

CONDENSER SECTION									
BOTTOM HEAT PIPE (S/N-7)	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
TOP HEAT PIPE (S/N-5)	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
EVAPORATOR SECTION	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
SINGLE HEAT PIPE (S/N-3)	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****
	*****	*****	*****	*****	*****	*****	*****	*****	*****

FIGURE 7.11 Temperature Profile With Power to Evaporator Heater Number 2 Only

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
ARTERIES PRIMED)

CONDENSER SECTION

[illegible]

119.3 126.2

118.9444 126.6

EVAPORATOR	****	LOCATION	TEMP(DEG F)
	****	CONSTANT TEMP BATH	110.0
SECTION	****	AMBIENT AIR	68.4

HEATER	LOCATION	POWER (WATTS)
1	EVAP SAD W TAB	0
2	EVAP SAD W/G TAB	329.6
3	S/N-2 GAS RESER	0
4	S/N-1 GAS RESER	0
5	S/N-4 GAS RESER	0

118.9555 125.1


117. [**
** 117. C

[illegible]

**
 ** 116.4
 116.7**

[illegible]

FIGURE 7.12 Constant Temperature Bath Fluid Temperature-vs-Heat Pipe
Adiabatic Section Temperatures



8.0 EVALUATION AND CONCLUSIONS

The results of these tests satisfied the primary and secondary objectives on which they were based. The indicated turn-on and full-on temperatures of the individual heat pipes are very close to specification and the maximum heat transport capacities provide very adequate margins over that required for system operation. In addition, it was shown that the arteries-deprimed system capacity is approximately 11-12 percent of the arteries-primed maximum system capacity. Finally, the temperature profiles generated when operating only one evaporator heater and when varying the condenser sink (CTB) temperature gave an appreciation of the effects of RTV interface joints and saddle designs, as well as external environmental conditions, on the performance of this type of heat pipe thermal control system.

9.0 REFERENCES

1. 30-Centimeter Ion Thrust Subsystem Design Manual. NASA TM-79191, 1979.
2. Antoniuk, D. and Luedke, E.E.; CTS-Type Variable Conductance Heat Pipes for SEP FM/PPU. (TRW; NASA Contract NAS 3-21130.) NASA CR-159550, 1979.

APPENDIX A DETAILED TEMPERATURE AND HEATER POWER DATA

Five types of figures can be found in Appendix A. The first three are plots of:

- (1) Temperature profiles along the heat pipes at up to fifteen (15) specific times during the test sequence. Where there was more than one thermocouple at a point along the heat pipe length (e.g., on the evaporator and adiabatic sections and on the gas reservoirs), the average temperature was plotted in these figures.
- (2) Temperature histories. Thermocouple histories were grouped as indicated in the following table.

Thermocouple Numbers	Location
1-10	Evaporator temperatures
11-16	Adiabatic section temperatures
21-30	First heat pipe condenser and cooling tube temps
31-40	Second heat pipe condenser and cooling tube temps
41, 57, 43-50	Third heat pipe condenser and cooling tube temps
51-56	Gas reservoir temperatures
58, 59	Constant temperature bath (CTB) temperature and ambient air temperature

- (3) Power histories of the two evaporator heaters (numbers 1 and 2) and the three gas reservoir heaters (numbers 3, 4, 5).

The last two types are instantaneous temperature-profile schematics which show the system response at the times of:

- (4) Individual heat pipe turn-on condition (when thermocouple 21, 31, or 41 are within 5°F of the adiabatic section temperatures), and,
- (5) Individual heat pipe or system full-on condition (equilibrium condition with 220 watts/heat pipe applied to evaporator heaters).

The sequence in which the data is presented is shown in the following table:

1979 Test Date	Run No.	Module Config.	Heat Pipes Oper.	Test Conditions: Arteries	Figure Type				
					1	2	3	4	5
					First Figure of Given Type				
5-17	1	B	3,5,7	Primed	A-1.1	A-1.3	A-1.10	A-1.11	A-1.14
5-21	1		3	Primed	A-2.1	A-2.3	A-2.10	A-2.11	A-2.12
5-29	1		5	Primed	A-3.1	A-3.3	A-3.10	A-3.11	A-3.12
5-30	1		7	Primed	A-4.1	A-4.3	A-4.10	A-4.11	A-4.12
5-31	1		3,5,7	Deprimed	A-5.1	A-5.3	A-5.10	A-5.11	A-5.14
7-3	1	A	2,1,4	Primed	A-6.1	A-6.3	A-6.10	A-6.11	A-6.14
7-19	1		2	Primed	A-7.1	A-7.3	A-7.10	A-7.11	A-7.12
7-23	1		1	Primed	A-8.1	A-8.3	A-8.10	A-8.11	A-8.12
7-24	1		4	Primed	A-9.1	A-9.5	A-9.12	A-9.13	A-9.14
	2		2,1,4	Deprimed	A-9.3	A-9.5	A-9.12	A-9.13	A-9.16
7-25	1		2,1,4	Primed ¹	A-10.1	A-10.5	A-10.12	A-10.13	---
	2		2,1,4	Primed ²	A-10.3	A-10.5	A-10.12	---	A-10.15

¹Varying sink temperature.


²Repeat of 7-3-79 test run.

FIGURE A-1.1
 SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
 ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
 (ARTERIES PRIMED)

DATE
 51779

TIME
 1055
 1105
 1110
 1115
 1120
 1129
 1150
 1153
 1155
 1159
 1203
 1315
 1505
 1645
 1649

□ □ □ + X ○ + X X Z Y X X X X - ★






FIGURE A-1.3

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
(ARTERIES PRIMED)

DATE
51779




FIGURE A-1.4

SEP BIMCO VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
(ARTERIES PRIMED)

DATE
51779




FIGURE A-1.5
 SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
 ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
 (ARTERIES PRIMED)

DATE
 51779




FIGURE A-1.6

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
(ARTERIES PRIMED)

DATE
51779




FIGURE A-1.7

SEP BIMCO VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
(ARTERIES PRIMED)

DATE
51779






FIGURE A-1.8
 SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
 ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
 (ARTERIES PRIMED)

DATE
 51779



T/C NO
 51
 52
 53
 54
 55
 56
 50 4 + X 0





---JAH

FIGURE A-1.9

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
(ARTERIES PRIMED)

DATE
51779





USE PIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
(ARTERIES PRIMED)

CONDENSER SECTION

BOTTOM
HEAT PIPE
(S/N-7)

[illegible]

TOP
HEAT PIPE
(S/N-5)

[illegible]EVAPORATOR
SECTION

LOCATION TEMP (DEG F)
CONSTANT TEMP BATH 114.0
AMBIENT AIR 69.8

HEATER	LOCATION	POWER (WATTS)
1	EVAP SAD W TAB	29.8
2	EVAP SAD W/O TAB	29.8
3	S/N-3 GAS RESER	.0
4	S/N-5 GAS RESER	.0
5	S/N-7 GAS RESER	.0

SINGLE
HEAT PIPE
(S/N-3)

100.5**	94.6***	76.0***	69.6***	67.2***	64.8***	61.5***	55.7***	34.9***	36.1	-89.1
**	*	*	*	*	*	*	*	*	*	*
100.4										
**										
100.5**										
**										
100.4										
**										
100.5**										
**										
100.4										
**										
100.5**										
**										
100.4										
**										
100.5**										
**										
100.4										
**										
100.5**										
**										
100.4										
**										
100.5**										
**										
100.4										
**										
100.5**										
**										
100.4										
**										
100.5**										
**										
100.4										
**										
100.5**										
**										
100.4										
**										
100.5**										
**										
100.4										
**										
100.5**										
**										
100.4										
**										
100.5**										
**										
100.4										
**										
100.5**										
**										
100.4										
**										
100.5**										
**										
100.4										
**										
100.5**										
**										
100.4										
**										
100.5**										
**										
100.4										
**										
100.5**										
**										
100.4										
**										
100.5**										
**										
100.4										
**										
100.5**										
**										

SEP RIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
(ARTERIES PRIMED) TEST DATE = 51779 TIME = 1145

[illegible]

	EVAPORATOR SECTION	HEATER	LOCATION	TEMP(°C)	POWER(WATTS)
***		1	EVA P SAD W TAB	113.8	29.8
***		2	EVA P SAD W/O TAB	69.7	29.8
***		3	S/N-3 GAS RESER		.0
***		4	S/N-5 GAS RESER		.0
***		5	S/N-7 GAS RESER		.0
103.6					

103.4					

103.9					

103.3					

[illegible]


```

USER BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
ARTERIES PRIMED)
TEST DATE = 51779    TIME = 1150

```

[illegible][illegible]

103.2*** 103.1

LOCATION	TEMP (DEG F)
CONSTANT TEMP BATH	113.6
AMBIENT AIR	69.7

HEATER	LOCATION	POWER (WATTS)
1	EVAP SAD W TAB	29.8
2	EVAP SAD W/O TAB	29.8
3	S/N-3 GAS RESER	.0
4	S/N-5 GAS RESER	.0
5	S/N-7 GAS RESER	.0

[illegible]

SEP RTMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
(ARTERIES PRIMED)
TEST DATE = 51779 TIME = 1300

```

BOTTOM
HEAT PIPE
(5/N-7)
** 118.5*** 120.8*** 116.2*** 118.9*** 119.2*** 117.2*** 90.2*** -109.1***** -73.8
124.3** 116.5
** 123.5
**

```

```


TOP
HEAT PIPE
(S/N-5)
*****
** 120.8*** 121.8*** 121.0*** 120.7*** 121.0*** 120.4*** 117.5*** 79.3*** -109.8*** -65.1
124.9** 120.4
** 124.5
*****

```

HEATER	LOCATION	TEMP(°C)	TEMP(°F)
1	EVAP SAD W TAB	112.2	112.2
2	EVAP SAD W/O TAB	70.3	70.3
3	S/N-3 GAS RESER		
4	S/N-5 GAS RESER		
5	S/N-7 GAS RESER		

[illegible]

FIGURE A-2.1
SEP BIMCO VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE SYN-3 OPERATING



DATE
52179

FIGURE A-2.2
SEP BIMCD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-3 OPERATING




FIGURE A-2.3
SEP BIMCO VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-3 OPERATING

DATE
52179




FIGURE A-2.4
SEP BIMCO VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-3 OPERATING

DATE
52179




FIGURE A-2.5

SEP BIMCO VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-3 OPERATING

DATE
52179




FIGURE A-2.6
SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-3 OPERATING





FIGURE A-2.7


SEP BIMCO VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-3 OPERATING

DATE
52179



T/C NO
41
57
43
44
45
46
47
48
49
50

0 4 + X 4 Z Z Y



---JAH

FIGURE A-2.8

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
 ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-3 OPERATING

DATE
 52179




FIGURE A-2.9

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-3 OPERATING

DATE
52179





FIGURE A-2.10
 SEP BIMCO VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION---SERIAL NO. 1
 ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-3 OPERATING



USEP PIMOD VARIABLE CONDUCTANCE HEAT PIPES-----MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-3 OPERATING

TEST DATE = 52179 TIME = 1115

BOTTOM
HEAT PIPE
(S/N-71)

[illegible]

102.3 ***** 102.6

**

593.2*** 193.6

EVAPORATOR
SECTION

LOCATION	TEMP (DEG F)
CONSTANT TEMP BATH	111.0
AMBIENT AIR	70.2

	HEATER	LOCATION	POWER(WATTS)
102.9*****	1	EVAP SAD W TAB	29.8
*****	2	EVAP SAD W/O TAB	29.8
*****	3	S/N-3 GAS PESER	0
*****	4	S/N-5 GAS PESER	17.4
*****	5	S/N-7 GAS PESER	12.1
102.5*****			

5-201 ***8-101

SINGLE
HEAT PIPE
(S/N-31)

** 99.9 *****
100.4** *****

* *****
***** 70.9*** 68.8*** 63.4*** 40.5*** -15.0*** -101.9
* 94.9*** 96.1*** 75.6*** 70.2*** 41.1 *****

92.2 *****

USEP PIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE R CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-3 OPERATING

TEST DATE = 52179 TIME = 1315

```

BOTTOM
HEAT PIPE
(S/N-7)

** 102.4*** ** 85.4*** ** 93.6*** ** 76.8*** ** 77.0*** ** 84.8*** ** 109.5*** ** 126.C*** ** 145.2*** ** 147.5
139.C** 99.8
** 139.8

```

[illegible]

EVAPORATOR	*****	LOCATION	TEMP(DEG F)
SECTION	*****	CONSTANT TEMP BATH	112.2
	*****	AMBIENT AIR	77.6

HEATFLP	LOCATION	POWER(WATTS)
1	EVAP SAD W TAB	108.3
2	EVAP SAD W/O TAB	108.3
3	S/A-3 GAS PESER	.0
4	S/A-5 GAS PESER	30.1
5	S/A-7 GAS PESER	23.1

[illegible]

DATE
52979

FIGURE A-3.1
SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-5 OPERATING




FIGURE A-3.2
SEEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-5 OPERATING




FIGURE A-3.3

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-5 OPERATING

DATE
52979




FIGURE A-3.4

SEP BIMCO VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-5 OPERATING

DATE
52979




FIGURE A-3.5
SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-5 OPERATING

DATE
52979




FIGURE A-3.6

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-5 OPERATING

DATE
52979




FIGURE A-3.7

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-5 OPERATING

DATE
52979




FIGURE A-3.8

SEP BIMCO VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-5 OPERATING

DATE
52979





FIGURE A-3.9

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-5 OPERATING

DATE
52979





SEP RIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1 TEST DATE = 52979 TIME = 1500
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-5 OPERATING

CONDENSER SECTION[illegible][illegible]

129.7 129.7

130.8*** 129.8

***	LOCATION	TEMP(DEG F)
***	CONSTANT TEMP BATH	112.1
***	AMBIENT AIR	71.2

HEATER	LOCATION	POWER(WATTS)
1	FVAP SAD W TAB	110.3
2	EVAP SAD W/O TAB	110.3
3	S/N-3 GAS RESER	13.1
4	S/N-5 GAS RESER	.0
5	S/N-7 GAS RESER	17.1


136.0*** 136.1

SINGLE	** 108.1	*
HEAT PIPE	111.6**	*
(S/N-3)	* 75.3***	*
	75.4	*
	73.6***	*
	74.1***	*
	74.0***	*
	75.4***	*
	79.3***	*
	88.1***	*
	111.5***	*
	141.1***	*
	108.4	*
	139.8	*

FIGURE A-4.1

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-7 OPERATING

DATE
53079



DATE
53079

FIGURE A-4.2
SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-7 OPERATING




FIGURE A-4.3

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
 ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-7 OPERATING

DATE
 53079




FIGURE A-4.4

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-7 OPERATING

DATE
53079




FIGURE A-4.5

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-7 OPERATING

DATE
53079




FIGURE A-4.6
SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-7 OPERATING

DATE
53079




FIGURE A-4.7

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-7 OPERATING

DATE
53079




FIGURE A-4.8
 SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
 ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-7 OPERATING

DATE
 53079





FIGURE A-4.9

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
 ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-7 OPERATING

DATE
 53079






FIGURE A-4.11

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1. TEST DATE = 53079 TIME = 1030
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-7 OPERATING

CONDENSER SECTION

BOTTOM
HEAT PIPE
(S/N-7)

** 93.5*** 87.4*** 68.4*** 70.1*** 64.6*** 56.8*** 37.0***-107.1***
** 92.3** 98.3** 37.8 *****-102.6
**

TOP
HEAT PIPE
(S/N-5)

** 71.0*** 71.2*** 71.7*** 73.4*** 78.5*** 89.4*** 108.2*** 116.0*** 133.0***
** 71.4** 81.1** 31.2** 119.7 ***** 131.9
**

100.6*** 101.4

101.4*** 101.3

101.2*** 101.7

102.3*** 101.6

101.1*** 101.1

84.1** 82.9

SINGLE
HEAT PIPE
(S/N-3)

** 71.5*** 71.4*** 72.2*** 74.3*** 79.1*** 88.6*** 103.1*** 129.5*** 136.5***
** 71.7** 71.7** 126.6 ***** 134.8
**

LOCATION TEMPI(DEG F)
CONSTANT TEMP BATH 112.2
AMBIENT AIR 75.1

HEATER LOCATION POWER(WATTS)
1 EVAP SAD W TAB 30.3
2 EVAP SAD W/O TAB 30.3
3 S/N-3 GAS RESER 15.3
4 S/N-5 GAS RESER 27.1
5 S/N-7 GAS RESER 0.0

USEP PIMOD VARIABLE CONDUCTANCL HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-7 OPERATING

TEST DATE = 53079 TIME = 1155

[illegible]


EVAPORATOR	LOCATION	TEMP (DEG F)
SECTION	CONSTANT TEMP	112.1
	AMBIENT AIR	70.6
131.0	130.5	
132.3	132.2	

HEATER	LOCATION	POWER(WATTS)
1	EVAP SAD W TAB	110.3
2	EVAP SAD W/O TAB	110.3
3	S/N-3 GAS RESER	12.1
4	S/N-5 GAS RESER	26.1
5	S/N-7 GAS RESER	.0

[illegible]

FIGURE A-5.1

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
(ARTERIES DEPRIMED)






FIGURE A-5.3

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
(ARTERIES DEPRIMED)

DATE
53179




FIGURE A-5.4
 SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
 ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
 (ARTERIES DEPRIVED)

DATE
 53179





FIGURE A-5.5


SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
(ARTERIES DEPRIVED)

DATE
53179



T/C NO
21
22
23
24
25
26
27
28
29
30

00 4 + X 0 + X Z Y



---JPH

FIGURE A-5.6

SEP BIMCO VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
(ARTERIES DEPRINED)

DATE
53179




FIGURE A-5.7
SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
(ARTERIES DEPRIVED)

DATE
53179






FIGURE A-5.8

SEP BIMCO VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
(ARTERIES DEPRIMED)

DATE
53179



T/C NO
51
52
53
54
55
56
□ □ 4 + X ◇



---JPH


DATE 53179



— 1987

FIGURE A-5.10
 SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
 ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
 (ARTERIES DEPRIVED)

DATE
 53179



HEATER
 1
 2
 3
 4
 5
 004+X




FIGURE A-5.11

SEP RIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1 TEST DATE = 53179 TIME = 958
 ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
 (ARTERIES DEPRIMED)

CONDENSER SECTION

BOTTOM
 HEAT PIPE
 (S/N-71) 101.2*** 73.1*** 67.1*** 53.8*** 52.2*** 57.7*** 50.6*** 40.0*** 14.4*** -104.1*** -94.5

TOP
 HEAT PIPE
 (S/N-3) 100.4*** 84.9 98.7 75.2*** 70.6*** 69.7*** 69.3*** 57.0*** 56.5*** 12.2*** -109.0*** -96.7

103.1*** 103.0

104.0*** 103.9

EVAPORATOR
 SECTION

HEATER	LOCATION	POWER (WATTS)	TEMP (DEG F)
1	EVAP SAD N. TAB	30.1	85.2
2	EVAP SAD W/O TAB	30.1	59.7
3	S/N-3 GAS PESER	0.0	
4	S/N-5 GAS RESER	0.0	
5	S/A-7 GAS RESER	0.0	

104.4*** 104.0

103.5*** 103.6

SINGLE
 HEAT PIPE
 (S/N-3)

102.1*** 97.5*** 73.5*** 65.2*** 62.0*** 57.6*** 50.1*** 36.6*** 4.9*** -106.2*** -99.0

```

USER PIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE B CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
ARTERIES DEPRIMED
TEST DATE = 53179 TIME = 1105

```

99

FIGURE A-5.13

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES--MODULE B CONFIGURATION SERIAL NO. 1 TEST DATE = 5/17/79 TIME = 1205
 ACCEPTANCE AND CHARACTERIZATION TESTS--ALL 3 HEAT PIPES OPERATING
 (ARTERIES DEPRIVED)

CONDENSER SECTION

BOTTOM
 HEAT PIPE
 (S/N-7) 114.5** 98.2** 76.3*** 54.4*** 60.1*** 56.1*** 51.6*** 45.9*** 21.8*** -115.5*** -91.4

TOP
 HEAT PIPE
 (S/N-5) 119.4** 102.3** 98.2*** 94.5*** 92.2*** 87.3*** 81.9*** 75.0*** 22.0*** -17.6*** -91.5

115.2*** 115.0

135.4*** 136.4

EVAPORATOR SECTION

LOCATION TEMP (DEG F)
 CONSTANT TEMP BATH 97.9
 AMBIENT AIR 70.5

HEATER LOCATION POWER (WATTS)
 1 EVAP. SAD. W. TAB 50.3
 2 EVAP. SAD. W/O TAB 50.3
 3 S/N-3 GAS PESER 0
 4 S/N-5 GAS PESER 0
 5 S/N-7 GAS PESER 0

145.0*** 144.9

172.4*** 171.7

117.3*** 117.4

SINGLE HEAT PIPE (S/N-3)

114.7** 114.1
 112.7*** 112.0*** 117.0*** 111.9*** 108.9*** 81.4*** 52.5*** 9.7*** -98.7*** -91.9

SEP RIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE R CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
(ARTICLES DEPRIMED) TEST DATE = 53179 TIME = 1245

[illegible]

FIGURE A-6.1

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
(ARTERIES PRIMED)




FIGURE A-6.2
 SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
 ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
 (ARTERIES PRIMED)




FIGURE A-6.3
SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
(ARTERIES PRIMED)

DATE
70379




FIGURE A-6.4

SEP BIMCO VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1.
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
(ARTERIES PRIMED)

DATE
70379






FIGURE A-6.5
SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
(ARTERIES PRIMED)

DATE
70379



DATE
70379

FIGURE A-6.6
SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
(ARTERIES PRIMED)



USE BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
(ARTERIES PRIMED)

DATE 70379




FIGURE A-6.8

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
(ARTERIES PRIMED)

DATE
70379




FIGURE A-6.9
SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
(ARTERIES PRIMED)

DATE
70379




FIGURE A-6.10
SEP BIMCO VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
(ARTERIES PRIMED)




FIGURE A-6.11

SEP BIMOD VARIABLE CONJUGIANCE HEAT PIPES--MODULE A CONFIGURATION SERIAL NO. 1 TEST DATE = 7U379 TIME = 1200
 ACCEPTANCE AND CHARACTERIZATION TESTS--ALL 3 HEAT PIPES OPERATING
 (ARTERIES PRIMED)

CONDENSER SECTION

SINGLE HEAT PIPE (S/N-2)	81.6**	71.3***	70.4***	69.8***	59.3***	66.7***	57.5***	64.2***	53.3***-104.1*****
	**	**	**	**	**	**	**	**	54.5 *****-102.3
	**	**	**	**	**	**	**	**	*****

EVAPORATOR SECTION	99.3***	99.9							
	***	***							
	***	***							

TOP HEAT PIPE (S/N-4)	97.2**	97.4							
	***	***							
	***	***							

BOTTOM HEAT PIPE (S/N-1)	97.1**	97.1							
	***	***							
	***	***							


```

SEP 01WD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
(ARTIES PRINTED)
TEST DATE = 70379 TIME = 1206

```

113

SEP BIWOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1 TEST DATE = 70379 TIME = 1225
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
ARTICLES PRINTED)

114

FIGURE A-6.14

SEP 81MOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1 TEST DATE = 70379 TIME = 1450
 ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
 (ARTERIES PRIMED)

CONDENSER SECTION

SINGLE
 HEAT PIPE
 (S/N=2)

 ** 120.6*** 118.9*** 119.2*** 113.3*** 117.4*** 117.8*** 116.2*** 85.0***-110.3***
 124.7** 118.0
 ** 122.9
 **

 ** 92.3 *****-90.3

130.0*** 133.7

131.2*** 133.5

EVAPORATOR
 SECTION
 LOCATION TEMP(DEG F)
 CONSTANT TEMP BATH 109.9
 AMBIENT AIR 68.3

HEATER LOCATION POWER(WATTS)
 1 EVAP SAD W TAB 329.6
 2 EVAP SAD W/O TAB 329.6
 3 S/N-2 GAS RESER .0
 4 S/N-1 GAS RESER .0
 5 S/N-4 GAS RESER .0

132.2*** 135.3

131.3*** 132.9

TOP
 HEAT PIPE
 (S/N=4)
 ** 123.8
 124.0**

 ** 120.8*** 122.0*** 121.2*** 120.3*** 120.2*** 117.6*** 101.2*** -96.4***
 119.9
 107.7 ***** -62.9

BOTTOM
 HEAT PIPE
 (S/N=1)
 ** 123.9
 123.9**

 ** 118.6*** 120.6*** 120.0*** 120.0*** 119.4*** 119.3*** 117.1*** 91.7*** -98.2***
 118.2
 108.6 ***** -79.8

SEP BIMOD VARIABLE: CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-2 OPERATING

TEMPERATURE (DEG F)




FIGURE A-7.2
SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-2 OPERATING

DATE
71979




FIGURE A-7.3

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-2 OPERATING

DATE
71979





FIGURE A-7.4


SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-2 OPERATING

DATE
71979



T/C NO
11
12
13
14
15
16

□ ○ + ×



---JAN

FIGURE A-7.5
SEP BIMCO VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-2 OPERATING

DATE
71979




FIGURE A-7.6
 SEP BIMCO VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
 ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-2 OPERATING

DATE
 71979




FIGURE A-7.7

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-2 OPERATING

DATE
71979




FIGURE A-7.8

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-2 OPERATING

DATE
71979




FIGURE A-7.9

SEP BIMCO VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-2 OPERATING

DATE
71979





FIGURE A-7.10
 SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
 ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-2 OPERATING

DATE
 71979



SEP-01MOD-VARIABLE-CONDUCTANCE-HEAT PIPES--MODULE A CONFIGURATION SERIAL NO. 1 TEST DATE = 71979 TIME = 1025
ACCEPTANCE AND CHARACTERIZATION TESTS--HEAT PIPE S/N-2 OPERATING

[illegible][illegible]

FIGURE A-7.12

SEP RIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1 TEST DATE = 71979 TIME = 1125
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-2 OPERATING

CONDENSER SECTION

SINGLE
HEAT PIPE
(S/N-2)
121.3** 114.2
** 118.6
**

125.2*** 126.6

126.1*** 126.9

125.9*** 127.2

126.4*** 127.7

125.8*** 126.9

95.9
99.1**
* 75.3*** 73.3*** 73.2*** 73.5*** 75.5*** 79.6*** 87.9*** 107.5*** 137.7*** 138.3
75.4

EVAPORATOR
SECTION
126.1*** 126.9

125.9*** 127.2

126.4*** 127.7

125.8*** 126.9

95.9
99.1**
* 75.3*** 73.3*** 73.2*** 73.5*** 75.5*** 79.6*** 87.9*** 107.5*** 137.7*** 138.3
75.4

TOP
HEAT PIPE
(S/N-4)
121.3** 114.2
** 118.6
**

125.2*** 126.6

126.1*** 126.9

125.9*** 127.2

126.4*** 127.7

125.8*** 126.9

95.9
99.1**
* 75.3*** 73.3*** 73.2*** 73.5*** 75.5*** 79.6*** 87.9*** 107.5*** 137.7*** 138.3
75.4

BOTTOM
HEAT PIPE
(S/N-1)
121.3** 114.2
** 118.6
**

125.2*** 126.6

126.1*** 126.9

125.9*** 127.2

126.4*** 127.7

125.8*** 126.9

95.9
99.1**
* 75.3*** 73.3*** 73.2*** 73.5*** 75.5*** 79.6*** 87.9*** 107.5*** 137.7*** 138.3
75.4

FIGURE A-8.1
SEP BIMCO VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-1 OPERATING

DATE
72379




FIGURE A-8.3

SEP BIMCO VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-1 OPERATING

DATE:
72379




FIGURE A-8.4

SEP BIMCO VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-1 OPERATING

DATE
72379




FIGURE A-8.5

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-1 OPERATING

DATE
72379




FIGURE A-8.6

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-1 OPERATING

DATE
72379




FIGURE A-8.7

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-1 OPERATING

DATE
72379




FIGURE A-8.8

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
 ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-1 OPERATING

DATE
 72379




FIGURE A-8.9

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
 ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-1 OPERATING

DATE
 72379





FIGURE A-8.10

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-1 OPERATING

DATE
72379



SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1 TEST DATE = 72379 TIME = 1025
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-1 OPERATING

[illegible]

FIGURE A-8.12

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES--MODULE A CONFIGURATION SERIAL NO. 1 TFSI DATE = 72379 TIME = 1515
ACCEPTANCE AND CHARACTERIZATION TESTS--HEAT PIPE S/N-1 OPERATING

CONDENSER SECTION

SINGLE HEAT PIPE (S/N-2)	*****								
	** 74.5*** 73.4*** 73.4*** 74.7*** 78.1*** 95.8*** 101.7*** 132.6*** 142.2***								
	97.3** 75.0 131.1 ***** 140.1								
	** 94.9								
**									

130.8*** 132.2									

131.4*** 132.8									

EVAPORATOR SECTION	*****								

131.7*** 132.3									

131.8*** 132.2									

130.2*** 130.6									

**									
** 104.3									
107.0**									
TOP HEAT PIPE (S/N-4)	*****								

	* 85.1*** 83.1*** 82.9*** 82.1*** 83.0*** 89.6*** 103.4*** 132.7*** 145.5***								
	84.8 133.7 ***** 146.3								

**									
** 122.5									
122.9**									
BOTTOM HEAT PIPE (S/N-1)	*****								

	* 116.5*** 118.9*** 118.2*** 113.2*** 119.1*** 118.2*** 117.0*** 91.4***-112.1***								
	116.3 100.6 ***** -94.9								

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-4 OPERATING

DATE 72479




FIGURE A-9.2
 SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
 ACCEPTANCE AND CHARACTERIZATION TESTS---HEAT PIPE S/N-4 OPERATING





FIGURE A-9.3
 SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
 ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
 (ARTERIES DEPRIVED)



SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
(ARTERIES DEPRIMED)




FIGURE A-9.5

SEP BIMCO VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---(1) HEAT PIPE S/N-4 OPERATING, AND
(2) ALL 3 HEAT PIPES OPERATING (ARTERIES DEPRIMED)

DATE
72479




FIGURE A-9.6
SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---(1) HEAT PIPE S/N-4 OPERATING, AND
(2) ALL 3 HEAT PIPES OPERATING (ARTERIES DEPRIVED)

DATE
72479




FIGURE A-9.7

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
 ACCEPTANCE AND CHARACTERIZATION TESTS---(1) HEAT PIPE S/N-4 OPERATING, AND
 (2) ALL 3 HEAT PIPES OPERATING (ARTERIES DEPRIVED)

DATE:
 72479




FIGURE A-9.8

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
 ACCEPTANCE AND CHARACTERIZATION TESTS---(1) HEAT PIPE S/N-4 OPERATING. AND
 (2) ALL 3 HEAT PIPES OPERATING (ARTERIES DEPRIVED)

DATE
 72479




FIGURE A-9.9
 SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1.
 ACCEPTANCE AND CHARACTERIZATION TESTS---(1) HEAT PIPE S/N-4 OPERATING, AND
 (2) ALL 3 HEAT PIPES OPERATING (ARTERIES DEPRIMED)

DATE
 72479




FIGURE A-9.10

SEP BIMCO VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
 ACCEPTANCE AND CHARACTERIZATION TESTS---(1) HEAT PIPE S/N-4 OPERATING, AND
 (2) ALL 3 HEAT PIPES OPERATING (ARTERIES DEPRIVED)

DATE
 72479





FIGURE A-9.11

SEP BIMCO VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---(1) HEAT PIPE S/N-4 OPERATING. AND
(2) ALL 3 HEAT PIPES OPERATING (ARTERIES DEPRIVED)

DATE
72479



T/C NC
58
59

FIGURE A-9.12
 SEP BIMCO VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
 ACCEPTANCE AND CHARACTERIZATION TESTS---(1) HEAT PIPE S/N-4 OPERATING, AND
 (2) ALL 3 HEAT PIPES OPERATING (ARTERIES DEPRIVED)

DATE
 72479




FIGURE A-9.13

SEP RIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1 TEST DATE = 72479 TIME = 1010
 ACCEPTANCE AND CHARACTERIZATION TESTS---(1) HEAT PIPE S/N-4 OPERATING, AND
 (2) ALL 3 HEAT PIPES OPERATING (ARTERIES DEPRIMED)

CONDENSER SECTION

SINGLE									

HEAT PIPE									
(S/N-2)									
82.1**		72.2***		71.7***		71.9***		73.1***	
72.4		72.4		71.9***		71.9***		73.1***	
** 81.2		** 81.2		71.9***		71.9***		73.1***	
**		**		71.9***		71.9***		73.1***	
***		***		71.9***		71.9***		73.1***	
101.4***		101.4***		71.9***		71.9***		73.1***	
***		***		71.9***		71.9***		73.1***	
***		***		71.9***		71.9***		73.1***	
***		***		71.9***		71.9***		73.1***	
102.2***		102.2		71.9***		71.9***		73.1***	
***		***		71.9***		71.9***		73.1***	
***		***		71.9***		71.9***		73.1***	
***		***		71.9***		71.9***		73.1***	
102.0***		102.3		71.9***		71.9***		73.1***	
***		***		71.9***		71.9***		73.1***	
***		***		71.9***		71.9***		73.1***	
***		***		71.9***		71.9***		73.1***	
***		***		71.9***		71.9***		73.1***	
101.6***		102.2		71.9***		71.9***		73.1***	
***		***		71.9***		71.9***		73.1***	
***		***		71.9***		71.9***		73.1***	
***		***		71.9***		71.9***		73.1***	
***		***		71.9***		71.9***		73.1***	
100.9***		101.1		71.9***		71.9***		73.1***	
***		***		71.9***		71.9***		73.1***	
***		***		71.9***		71.9***		73.1***	
***		***		71.9***		71.9***		73.1***	
98.4**		98.8		71.9***		71.9***		73.1***	
98.8		98.8		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	
*****		*****		71.9***		71.9***		73.1***	

FIGURE A-9.14

SEP PIWOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1 TEST DATE = 72479 TIME = 1135
 ACCEPTANCE AND CHARACTERIZATION TESTS---(1) HEAT PIPE S/N-4 OPERATING, AND
 (2) ALL 3 HEAT PIPES OPERATING (ARTERIES DEPRIMED)

CONDENSER SECTION

SINGLE
 HEAT PIPE
 (S/N-2) *****
 ** 75.1*** 74.0*** 74.2*** 75.6*** 79.2*** 97.2*** 103.3*** 135.0*** 143.5***
 ** 98.3** 75.5 ***** 133.2 ***** 141.4
 ** 95.7 *****
 ** *****

132.0*** 132.8

132.5*** 133.1

EVAPORATOR SECTION LOCATION TEMP (DEG F)
 CONSTANT TEMP BATH 114.7
 AMBIENT AIR 71.1

HEATER LOCATION POWER (WATTS)
 1 EVAP SAD W TAB 110.0
 2 EVAP SAD W/2 TAB 110.0
 3 S/N-2 GAS RESER 20.3
 4 S/N-1 GAS RESER 25.0
 5 S/N-4 GAS RESER 9.0

131.5*** 133.4

130.7*** 130.9

TOP 122.9**
 HEAT PIPE
 (S/N-4) *****
 * 118.8*** 120.2*** 119.9*** 117.7*** 118.9*** 119.0*** 117.5*** 100.4*** -114.0***
 118.2 ***** 107.7 ***** -77.9

105.0** 104.3

BOTTOM 105.0**
 HEAT PIPE
 (S/N-1) *****
 * 81.1*** 76.7*** 75.9*** 76.1*** 79.0*** 96.0*** 101.6*** 128.7*** 142.2***
 81.7 ***** 129.0 ***** 143.7

SEP 81 MOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---(1) HEAT PIPE S/N-4 OPERATING, AND
(2) ALL 3 HEAT PIPES OPERATING (ARTERIES DEPRIMED) TEST DATE = 72479 TIME = 1340

154

USER PIMOD VARIABLE CONDUCTANCE HEAT PIPES--MODULE A CONFIGURATION SERIAL NO. 1 TEST DATE = 72479 TIME = 1625
ACCEPTANCE AND CHARACTERIZATION TESTS--(1) HEAT PIPE S/N-4 OPERATING, AND
(2) ALL 3 HEAT PIPES OPERATING (ARTERIES DEPRIVED)

155

FIGURE A-10.1
SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
(ARTERIES PRIMED---WITH VARYING SINK TEMP)




FIGURE A-10.2
 SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
 ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
 (ARTERIES PRIMED---WITH VARYING SINK TEMP)





FIGURE A-10.3
SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
(ARTERIES PRIMED---TO HEAT TRANSPORT CAPACITY LIMIT)

DATE
72579


TIME
1440
1445
1450
1500
1525
1530
1535

□ ○ + × ◇ ◆



DATE
72579

FIGURE A-10.4
SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING
(ARTERIES PRIMED---TO HEAT TRANSPORT CAPACITY LIMIT)



DATE:
72579

FIGURE A-10.5
SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING (ARTERIES
PRIMED---(1) WITH VARYING SINK TEMP. AND (2) TO HEAT TRANSPORT CAPACITY LIMIT)




FIGURE A-10.6

SEP BIMCO VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
 ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING (ARTERIES
 PRIMED---(1) WITH VARYING SINK TEMP. AND (2) TO HEAT TRANSPORT CAPACITY LIMIT)

DATE
 72579




FIGURE A-10.7

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
 ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING (ARTERIES
 PRIMED---(1) WITH VARYING SINK TEMP. AND (2) TO HEAT TRANSPORT CAPACITY LIMIT)

DATE
 72579




FIGURE A-10.8
 SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
 ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING (ARTERIES
 PRIMED---(1) WITH VARYING SINK TEMP. AND (2) TO HEAT TRANSPORT CAPACITY LIMIT)

DATE
 72579




FIGURE A-10.9
 SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
 ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING (ARTERIES
 PRIMED---(1) WITH VARYING SINK TEMP. AND (2) TO HEAT TRANSPORT CAPACITY LIMIT)

DATE
 72579




FIGURE A-10.10

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
 ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING (ARTERIES
 PRIMED---(1) WITH VARYING SINK TEMP. AND (2) TO HEAT TRANSPORT CAPACITY LIMIT)

DATE
 72579





FIGURE A-10.11
 SEP BIMCO VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
 ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING (ARTERIES
 PRIMED---(1) WITH VARYING SINK TEMP. AND (2) TO HEAT TRANSPORT CAPACITY LIMIT)

DATE
 72579




HEATER POWER (WATTS)

500.00
450.00
400.00
350.00
300.00
250.00
200.00
150.00
100.00
50.00
0.00

FIGURE A-10.12
SEP BIMCO VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING (ARTERIES
PRIMED---(1) WITH VARYING SINK TEMP. AND (2) TO HEAT TRANSPORT CAPACITY LIMIT)

DATE
72579




SEP 81 MOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1 TEST DATE = 72579 TIME = 920
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING (ARTERIES
PRIMED---(1) WITH VARYING SINK TEMP, AND (2) TO HEAT TRANSPORT CAPACITY LIMIT)

168

SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES---MODULE A CONFIGURATION SERIAL NO. 1
ACCEPTANCE AND CHARACTERIZATION TESTS---ALL 3 HEAT PIPES OPERATING (ARTERIES
PRINTED---(1)WITH VARYING SINK TEMP, AND (2) TO HEAT TRANSPORT CAPACITY LIMIT)

169



1. Report No. NASA TM-82635		2. Government Accession No.		3. Recipient's Catalog No.	
4. Title and Subtitle SEP BIMOD VARIABLE CONDUCTANCE HEAT PIPES ACCEPTANCE AND CHARACTERIZATION TESTS				5. Report Date August 1981	
				6. Performing Organization Code 506-55-22	
7. Author(s) Joseph A. Hemminger				8. Performing Organization Report No. E-857	
9. Performing Organization Name and Address National Aeronautics and Space Administration Lewis Research Center Cleveland, Ohio 44135				10. Work Unit No.	
				11. Contract or Grant No.	
12. Sponsoring Agency Name and Address National Aeronautics and Space Administration Washington, D. C. 20546				13. Type of Report and Period Covered Technical Memorandum	
				14. Sponsoring Agency Code	
15. Supplementary Notes					
16. Abstract A series of six heat pipes, similar in design to those flown on the Communications Technology Satellite Hermes, were fabricated and tested by TRW Space Systems Group for use by NASA Lewis Research Center in a prototype Solar Electric Propulsion BIMOD thrust module. This report documents the results of acceptance and characterization tests performed on the heat pipe subassemblies following their delivery to NASA. The performance of all the heat pipes met, or exceeded, design specifications.					
17. Key Words (Suggested by Author(s)) Heat pipes; Thermal control; Power processing unit; Solar electric propulsion			18. Distribution Statement Unclassified - unlimited STAR Category 34		
19. Security Classif. (of this report) Unclassified		20. Security Classif. (of this page) Unclassified		21. No. of Pages	
				22. Price*	

National Aeronautics and
Space Administration

Washington, D.C.
20546

Official Business

Penalty for Private Use, \$300

SPECIAL FOURTH CLASS MAIL
BOOK

Postage and Fees Paid
National Aeronautics and
Space Administration
NASA-451



NASA

POSTMASTER: If Undeliverable (Section 158
Postal Manual) Do Not Return
